

BRUHAT BANGALORE MAHANAGARA PALIKE
DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division
DRAFT TENDER SHEDULE COPY

**Name of Work: Construction of Public Sitting flatform of Karekallu,
Sidedahalli, Manjunatha Nagara , BTS Extn. Aralikatty & Mutturaya Katty
12th cross in Bagalagunte Ward No.14**

Sl	Description of Work	Unit	Qty	Rate to be Quoted	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	85.90		
2	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications	Cum	19.09		
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification	Cum	136.10		
4	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specifications MORTH Specification No.1600 & 2200	Tonne	10.89		

no of corrections - nil

9

5	Providing and laying flooring and steps machine cut granite slabs 40mm thick on cement mortar bed 1:6, 25 mm thick , and pointed with cement mortar 1:3 over existing cement concrete bed, including cost of materials, labour, curing complete as per specifications. Specification	Sqm	929.60		
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	225.00		

no of corrections - nil

Total. no of corrections - nil

Jayarama.K.

Signature of the Contractor

DTS Approved

[Signature]

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

[Signature]

Executive Engineer
Dasarahalli Division